

Cart Path replacement, James Connally Golf Course

Excavate and remove existing cart path - #4/#5 600 linear feet (can be dumped on site)

Dig cart cavity to prepare for new cart path - #4/#5, #8, #16, #17 2100 linear feet

Form new cart path to be 6 feet wide, 4" thick

Use 3000psi with #3 bar at 16" O.C. crossed

Broom finish

Pull forms and backfill and clean the work area.

Contractor to make copies of concrete invoices showing that 3,000 PSI concrete was poured.

As stated on the RFP, contractor and employees shall have a photo I.D. visible at all times. This I.D. shall state employee's name and company they work for.

THIS IS AT A GOLF COURSE. CONTRACTOR WILL NEED TO UNDERSTAND HOW THE GOLFERS PLAYING THROUGH WILL AFFECT HIS WORK SCHEDULE. THE MANDATORY PRE-PROPOSAL IS TO BE ABLE TO CLEARLY DESCRIBE TO CONTRACTOR HIS DUTIES DURING THIS PROJECT AND THE ROUTES HE IS TO TAKE.

There is a mandatory Pre-Bid meeting for all interested bidders to be held at the James Connally Pro Shop on 1:00 PM Tuesday, April 22nd, 2014 at the John Connally Pro Shop located at 7900 Concord Dr, Waco, TX

For Questions, attend the Pre-Bid meeting or contact:

Jake May
TSTC GLM/James Connally Golf Course
jacob.may@tstc.edu
254-799-6561

Please do not come out to the golf course without contacting Jake ahead of time.

